Maryland Historical Trust —State Historic Sites Inventory Form

Washington

Magi No.

DOE __yes __no

	·			
1. Nam	e (indicate	e preferred name)		
historic SH	ADE'S SCHOOL	HOUSE		
and/or common	Joseph S. I	Brown House		
2. Loca	ition			
street & number	1230 Meadov	w Branch Road		not for publication
city, town	Westminste	r <u>XX</u> vicinity of	f congressional distr	ict Sixth
state	Maryland	COL	_{unty} Carroll	
3. Clas	sification			
structure _ site object	Ownership public XX_ private both Public Acquisition in process being consider XX_ not_applicate	yes: restricted	entertainmen government	museum park XX private residence religious scientific transportation other:
4. Own	er of Prop	oerty (give name	es and mailing addre	esses of <u>all</u> owners)
name	Joseph S. Bro	own		
street & number	1230 Meado	ow Branch Road	telephon	e no.: 848-3658
city, town	Westminst	er st	ate and zip code M	aryland 21157
5. Loca	ition of Le	egal Descrip	otion	
courthouse, regis	stry of deeds, etc.	Carroll County	Courthouse Anne	x liber 437
street & number		55 N. Court St	reet	folio 66
city, town		Westminster	sta	ate MD
6. Repr	esentatio	on in Existin	g Historical St	urveys
title None		*		·
te			federal	state county loca
depository for su	rvey records			
city, town			sta	ate

7. Description

Survey No. CARR-807

Condition — excellent — good — ruins XX fair — unattered xX altered	Check one XX original site moved date of move	· · · · · · · · · · · · · · · · · · ·	gare en
---	---	---------------------------------------	---------

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

SUMMARY: Shade's Schoolhouse was built in 1890 and is representative of the one-story, gable-front brick schoolhouses built throughout Carroll County in the late 19th century. As with many of these structures, Shade's Schoolhouse was converted to residential use in the early 20th Originally the building was a three-bay by three-bay brick structure on a fieldstone foundation. The gable front main facade had a central entrance with four-over-four sash windows in the outer bays of the first story and a small window in the gable. The building has a gable roof with a brick chimney rising at the peak of the north gable end. one time, perhaps originally, the exterior was painted dark red with the mortar joints penciled in white. One story, shed-roofed frame additions have been built on the south and west elevations and a two story addition is at the northwest corner of the structure.

DESCRIPTION: Shade's Schoolhouse is located on the north side of Meadow Branch Road, approximately .6 mile west of Littlestown Pike. It was built on the northeast corner of the intersection of Meadow Branch and Shade's Schoolhouse Roads (Shade's Schoolhouse Road has since been closed as a through road). The building presently sits on a lot consisting of 71 1/2 square perches. The building sits close to Meadow Branch Road and the main facade faces south. There are no distinguishable landscape features remaining from its period of use as a schoolhouse.

Originally the building was a three-bay by three-bay brick structure on a fieldstone foundation. The brickwork was laid in common bond with single brick jack arches above the window and door openings. Evidence on the east elevation shows that at one time, perhaps originally, the exterior was painted dark red with the mortar joints penciled in white. The building has a gable roof, currently covered in standing seam sheet metal, with a brick chimney rising at the peak of the north gable end.

The gable front main facade had a central entrance with four-over-four sash windows in the outer bays of the first story and a small window in the gable. The east and west elevations had windows in each of the three bays. The window sash is six-over-six which apparently is a replacement for the original four-over-four sash. The west elevation also has a door between the second and third bays from the south, which may be of later construction.

MARYLAND HISTORICAL TRUST STATE HISTORIC SITES INVENTORY FORM Description (continued)

Survey No. CARR-807

Section 7 Page 2

The schoolhouse has been used for residential purposes since 1926, and one story, shed-roofed frame additions have been built on the south and west elevations and a two story addition is at the northwest corner of the structure.

The original plan was one-room, but the interior has been remodeled and partitioned into two rooms. There are no remaining interior features from the time when the structure served as a schoolhouse.

Period _ prehi: _ 1400 1500 1600 1700 1800 1900-	-1499 archeology-historic -1599 agriculture -1699 <u>XX</u> architecture -1799 art -1899 commerce	check and justify below community planning conservation economics education engineering exploration/settleme industry invention	g landscape architectur law literature military music	re religion science sculpture social/ humanitarian theater transportation other (specify)
Specific	dates 1890 - 177 - 187	Builder/Architect	John Senft, Build	ler
check:	Applicable Criteria: A and/or	BCD		
	Applicable Exception:	A _B _C _D _	EFG	
	Level of Significance:	national state	local	
Prepare	both a summary paragraph	of significance and	3	

Prepare both a summary paragraph of significance and a general statement of history and support.

SUMMARY: Shade's Schoolhouse was built in 1890 by the Carroll County Board of County School Commissioners. It replaced an earlier schoolhouse that sat on an adjoining parcel of land. The exact site of the original school is unclear, but historical maps indicate that it probably sat to the southeast of the present site. George Shade gave the land for the original schoolhouse in 1857 in a deed to the Trustees of Cottage Primary School District #1. The minutes of the School Commissioners of Carroll County provide the details around the construction of the 1890 schoolhouse, which was built by John Senft. The building was in use as a school until 1926 when it was sold by the Board of Education and it has been in private ownership since that time.

HISTORY: The Land Records of Carroll County show that Shade's Schoolhouse follows a typical pattern of creation and use for the one-room schoolhouses in the county. Most of these schoolhouses began in the early to mid-19th century when a private donor contributed land to a local board of schoolhouse trustees. These schoolhouses were then incorporated into the county system after the creation of a county school board as required by state law in 1862. During the late 19th century, the county school board tore down the earlier structures and built new schoolhouses to improve classroom facilities. Then, in the early 20th century, these schoolhouses were abandoned through the consolidation efforts of the county school board. The land and buildings of these properties were sold at public sale and most were converted to private residences.

The land for the original Shade's Schoolhouse was given on May 18, 1857 by George Shade to George Schaeffer, John F. Shade, and George W. Stoner, Trustees of Cattage Primary School District #1 in Carroll County (Land Records of Carroll County, Liber 22, Folio 468). The deed states that the property is "to be held in trust that the said land and schoolhouse in Primary School District #1 in said county the same to be used

Survey No. <u>CARR-807</u>
Section 8 Page 2

and occupied as and for a primary school house and for public religious worship and Sabbath school and for no other purpose whatsoever." The wording of the deed leaves open the possibility that there was a schoolhouse, perhaps maintained by the Shade family, on the property before this date.

In 1862, Maryland state law required the creation of county school boards in each Maryland county, and during the course of the late 19th century, the county boards assumed control of the schoolhouse previously maintained by the trustees of the local school districts. On September 23, 1890, the Board of County School Commissioners made an exchange of land with Lewis D. Wentz in order to acquire a new lot for Shade's Schoolhouse that would adjoin a new county road (Land Records of Carroll County, Liber 71, Folio 537-8).

The <u>Proceedings of the School Commissioners of Carroll County October 1876 - June 1892</u> (see attached excerpts) provide the details of the construction of the new Shade's Schoolhouse. The builder of the schoolhouse was John Senft who submitted a low bid of \$662.

The schoolhouse was sold by the Board of Education of Carroll County at public sale in 1926 (Land Records of Carroll County, Liber 148, Folio 405).

Survey No. CARR-807

Section 8 Page 3

Proceedings of the School Commissioners of Carroll County October 1876 -June 1892

Excerpts Relating to the Construction of Shade's Schoolhouse

Page 370

July 1, 1890

Shade's Schoolhouse

"President Grimes reported that he and the Secretary had arranged for an exchange of land with Lewis Wentz that would bring the school lot of Shade's school to bind on the two roads which will intesect at that point when the contemplated new county road is opened, the exchande to be made as soon as the road is definitely laid out and determined upon."

Page 373

July 28, 1890

Shade's Exchange

"President Grimes and the secretary were authorized and directed to make an exchange of land with Lewis Wentz, whose property adjoins Shade's school lot, giving him a part of the school lot for an equal amount of his land, so as to bring the school lot to bound on the road from Stonersville and to make arrangements for the erection of a new schoolhouse on the lot as soon as this exchange could be effected."

Page 384

October 7, 1890

Shade's Schoolhouse

"Bids were received for building a new brick schoolhouse for Shade's School from Frederick A. Byers for six hundred and ninety-five dollars (\$ 695.00), from John Senft for six hundred and sixty-two dollars (\$662.00) said house to be of the usual size and according to the usual specifications. The President and Secretary were authorized and directed to award the contract to John Senft, he being the lowest bidder."

Page 387 November 18, 1890 Shade's Schoolhouse

"The President and Secretary were authorized to make partial payment on the new house for Shades school, as soon as they were satisfied from inspection that the work was in accordance with the specifications and funds were available."

Survey No. CARR-807
Section 8 Page 4

Proceedings of the School Commissioners of Carroll County October 1876 -June 1892

Excerpts Relating to the Construction of Shade's Schoolhouse (Continued)

Page 388 January 5, 1891 Shade's Schoolhouse

"President Grimes reported that the new house for Shades school was completed and ready for inspection. He, Mr. Slingluff and the Secretary were appointed to inspect it and report at the next meeting."

Page 390 February 3, 1891 Shade's Schoolhouse

"President Grimes and the Secretary reported that they had inspected the new house for Shade's school, and found it according to the specifications, except that the windows were made with four panes to a window instead of four to a sash, as directed. They asked authority to have them changed and recommended that when this was done, the house be accepted and final settlement made with the contractor. It was so ordered."

Survey No. CARR-807
Section 8 Page 5

CARR-807 Shade's Schoolhouse: Chain-of-Title

437/66 5/7/1968 George M. & Malinda M. Miller 71 1/2 sq per to Joseph S. & Iris E. Brown

366/519 11/8/1963 William T. & Bessie Welty Sherman to George M. & Malinda M. Miller

261/108 5/4/1956 Earl N. & Mary A. Click to William T. & Bessie Welty Sherman

229/204 1/23/1954 Herbert H. Click, Surviving Jt. Tenant, to Earl N. & Mary A. Click

187/416 6/30/1941 Paul T. Case & Genevieve M. Diffendal to Richard R., Melvin E. & Herbert H. Click

148/405 12/15/1926 Board of Education of Carroll County to Paul T. Case 4 parcels:

1. Franklin Public School (38/457) 2. Shade's Schoolhouse

3. Pipe Creek Schoolhouse (44/243; 47/38)

4. Priestland Schoolhouse (3/67; 35/377)

71/537-538 9/23/1890 Exchange of Land through two deeds between the Board of County School Commissioners of Carroll County and Lewis D. Wentz; references for the original Shade's Schoolhouse lot are listed below:

22/468 5/18/1857 George Shade to 48 sq per George Schaeffer, John F. Shade, George W. Stoner, Trustees of Cottage Primary School

9. Major Bibliographical References

Survey No. CARR-807

Land Records of Carroll County, Md.

Proceedings of the School Commissioners of Carroll County, October
1876 -- June 1892.

Acreage of nominated property Ouadrangle name New Windsor, Md. Ouadrangle scale 1:24000 UTM References do NOT complete UTM references A	10. Ge	ographical Da	ita				
Zone Easting Northing C	Quadrangle nam	e New Windsor, Md		-	Quadrang	le scale 1:24	000
Verbal boundary description and justification List all states and counties for properties overlapping state or county boundaries state code county code 11. Form Prepared By The properties overlapping state or county boundaries code 11. Form Prepared By Description Noodle-Doosey Press date November 1986 Street & number P.O. Box 716 telephone (301) 374-2605	^	L L L L L L L L L L L L L L L L L L L		Zone Easting			
List all states and counties for properties overlapping state or county boundaries state code county code 11. Form Prepared By name/title Joe Getty organization Noodle-Doosey Press date November 1986 street & number P.O. Box 716 telephone (301) 374-2605	E						<u> </u>
state code county code 11. Form Prepared By name/title Joe Getty organization Noodle-Doosey Press date November 1986 street & number P.O. Box 716 telephone (301) 374-2605	Verbal bounda	ry description and justifica	tion				
tate code county code 11. Form Prepared By Iname/title Joe Getty Organization Noodle-Doosey Press date November 1986 Street & number P.O. Box 716 telephone (301) 374-2605				te or county bo	oundaries	code	
proganization Noodle-Doosey Press date November 1986 street & number P.O. Box 716 telephone (301) 374-2605	state	code	county				, all the second
organization Noodle-Doosey Press date November 1986 street & number P.O. Box 716 telephone (301) 374-2605	11. For	m Prepared B	У				
street & number P.O. Box 716 telephone (301) 374-2605	name/title J	oe Getty				,	
telephone (901) 977 2009	organization N	oodle-Doosey Press		date No	vember	1986	
sity or town Manchester state Maryland	street & number	P.O. Box 716		telephone	(301)	374-2605	
	city or town	Manchester		state	Maryla	ind	

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to:


Maryland Historical Trust

Shaw House

21 State Circle

Annapolis, Maryland 21401

(301) 269-2438





- CARR-807 SHADE'S SCHOOLHOUSE
- Carroll County, Md.
- Joe Getty November 1986

- Maryland Hist. Trust, Annapolis S & W elev. (camera fac ne) 2/3



- CARR-807 SHADE'S SCHOOLHOUSE
- Carroll County, Md.
- Joe Getty
- November 1986
- Maryland Hist. Trust, AnnapolisSouth elev. (camera fac.north)
- 7. 1/3



- CARR-807 SHADE'S SCHOOLHOUSE
- Carroll County, Md. Joe Getty
- November 1986
- Maryland Hist. Trust, Annapolis N & E elev. (camera fac. sw)
- 3/3